

GRIDALIGN

Coordination Opportunity Report

Georgia Power

Callaway Road - Thomson Primary 500 kV

Distance between closest known points: 20.05 km

Dominion Energy South Carolina

Hooks - Modoc 115/46 kV Rebuild

PROJECTS

- Project A: Callaway Road - Thomson Primary 500 kV, located in Georgia (operating utility unspecified in provided records).
- Project B: Hooks - Modoc 115/46 kV Rebuild, located in South Carolina (operating utility unspecified in provided records).

WHY GRIDALIGN FLAGGED THIS PAIR

GridAlign flagged this pair because their closest known points are 20.05 km apart, placing them within the under 40 km regional coordination category.

GEOGRAPHIC ANALYSIS

At 20.05 km apart, these projects are too distant to share local access corridors, rights-of-way, or immediate substation laydown areas. However, projects separated by under 40 km may still be close enough to share specialized equipment, skilled contractor pools, regional mobilization efforts, or broader construction planning across the Georgia-South Carolina border area.

TIMELINE ANALYSIS

Timeline compatibility appears plausible but cannot be fully confirmed:

- Project A is in planning with a stated start date of Spring 2027 and no recorded completion date.
- Project B is planned with a target completion date of December 31, 2027, but no recorded start date.

If Project B undergoes active construction during 2027, the build windows could potentially overlap during the spring, summer, or fall of 2027.

COORDINATION OPPORTUNITIES

If the construction schedules overlap, potential coordination opportunities include:

- Regional contractor sharing, if the same regional transmission line contractors are qualified to bid on both projects.

- Shared mobilization and demobilization of specialized heavy equipment, such as wire tensioners, pullers, or high-capacity cranes, if these resources are required by both jobs.
- Construction sequencing between the two builds, which could potentially allow specialized crews to transition directly from one site to the other.
- Coordinated freight deliveries and material staging using regional transportation corridors.

POTENTIAL BENEFITS

- Potential reduction in equipment mobilization and demobilization costs by coordinating regional contractor deployment.
- Improved regional labor utilization by offering continuous work for specialized transmission crews.
- Opportunity for joint logistics planning that may minimize regional supply chain bottlenecks.

RISKS AND LIMITATIONS

- Missing schedule details prevent confirmation of the exact overlap window.
- The projects reside in different states (Georgia and South Carolina), which may mean different operating utilities, independent regulatory processes, and separate contracting requirements.
- The scopes differ substantially: Project A involves new 500 kV lines and a new 500/230 kV substation, while Project B is a 6.5-mile 115/46 kV line rebuild. Differences in voltage class and construction type may require distinct equipment specifications and crew certifications.

FINAL ASSESSMENT

MEDIUM

Meaningful coordination appears plausible because both transmission projects are located 20.05 km apart and could potentially share regional resources during 2027. However, important uncertainty remains due to unconfirmed start and completion dates, cross-border jurisdictions, and differing voltage scopes.

RECOMMENDED NEXT STEP

Project managers from both utilities should hold an introductory regional planning call to exchange specific 2027 construction schedules and determine whether common transmission contractors or equipment can be shared.